



NOTES

Based upon the Ordnance Survey mapping with the permission of the controller of Her Majesty's Stationery Office - Crown copyright. Unauthorised reproduction may lead to prosecution or civil proceedings. L.B. Newham LA086517 1997.

- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED. GATE DETAILS ARE APPROXIMATE AND ARE FOR ESTIMATE PURPOSES ONLY.
- THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT CONTRACT DOCUMENTS.
- GATE & FENCING TO COMPLY TO BS 1772 UNO, ALL GATE COMPONENTS SHALL BE MILD STEEL AND GALVANISED.
- GATES TO BE PAINTED - COLOUR FOR ALL ELEMENTS DULUX HERITAGE RANGE INVISIBLE GREEN.
- ALL MEMBERS TO BE WELDED TOGETHER IN ACCORDANCE WITH RELEVANT BRITISH STANDARDS. ALL WELDS SHALL BE SMOOTH AND EVEN. WELD SPLATTERS SHALL BE REMOVED.
- SOLID GATE INFILL RAILINGS TO BE FULLY WELDED TO TOP & BTM RAILS.
- GATE HINGERS SHALL BE FABRICATED FROM 15mm THICK STEEL PLATE WITH 20mm DIA. STEEL PIN. STEEL PIN SHALL BE SECURED TO PREVENT REMOVAL OF GATE.
- STOP PLATE 100x40x6mm WELDED TO GATE POST WITH 10mm THICK NEOPRENE RUBBER STRIP FIXED TO STOP PLATE WITH COUNTER SINK SELF TAPPING SCREWS & SUITABLE ADHESIVE AS PER DETAIL. NEOPRENE RUBBER SHALL DAMPEN METAL CLOSING SOUND AND REQUIRES ENGINEERS APPROVAL PRIOR TO FABRICATION OF GATE.
- ALL BOLTS SHALL BE SECURITY TYPE WITH WASHERS. SIZE OF WASHERS SHALL BE SUITABLE FOR NUT AND BOLT SIZE.
- CLEARANCE BETWEEN THE GROUND AND THE UNDERSIDE OF THE GATE SHALL BE SITE CHECKED TO ENSURE THAT THE GATE SHALL NOT CLASH WITH SLOPING GROUND.
- ALL DIMENSIONS (MARKED) AND LEVELS SHALL BE SITE VERIFIED PRIOR TO COMMENCEMENT OF WORK. ANY DISCREPANCY BETWEEN THE LEVELS/DIMENSIONS SHOWN ON THE DRAWINGS AND THE ACTUAL SITE CONDITIONS SHALL BE NOTIFIED TO THE ENGINEER. AFFECTED WORKS SHALL ONLY BE PROGRESSED AS PER THE ENGINEER/CLERK OF WORKS INSTRUCTIONS.
- PROVIDE 20mm DIA. x 400mm DROP BOLT ASSEMBLY WITH SLEEVED HOUSING CAST IN CONCRETE IN OPEN AND CLOSED POSITION.
- SECURITY PADLOCK TO BE SUPPLIED BY OTHERS.
- WHERE NECESSARY ALL TREES SHALL BE PROTECTED & ROOT PROTECTION AREAS OBSERVED IN ACCORDANCE WITH BS5837:2012.
- THE POSITIONS OF ANY CONTRACTORS SITE ACCOMMODATION OR MATERIAL STORE ETC. SHALL BE AGREED WITH THE SUPERVISING OFFICER AND THE PARK AUTHORITY.
- THE CONTRACTOR SHALL TAKE ALL RESPONSIBLE MEASURES TO PROTECT EXISTING UTILITIES AND SERVICES AND BEING DAMAGED. ANY DAMAGE CAUSED SHALL BE MADE GOOD OR REPLACED AT NO EXTRA COST TO THE CONTRACTOR.



**PROPOSED SCHEME GENERAL ARRANGEMENT
PHASE 1
1:200**




**TYPICAL DOUBLE GATE DETAILS
(VIEW FROM HAM PARK ROAD)
1:25**


VERTICAL PALES TO BE 20x20mm SOLID BAR POINT TO VIEW TO MATCH EXISTING RAILINGS. FINALS TO MATCH EXISTING DESIGN.
FIX INFILL PANELS TO NEW POSTS.
EXISTING FENCE POST, STAY AND BRICKWORK RETURN TO REMAIN.
EXISTING POST, STAY BRICKWORK RETURN & CAPPING TO REMAIN.

CONTRACTOR TO OBSERVE CARE WHERE REMOVING EXISTING BRICKWORK & CONCRETE TO FORM NEW OPENING FOR GATE. RESULTING BRICKWORK & COPINGS TO BE CLEANED & GENTLY STORED ON SITE FOR COLLECTION BY CLIENT.

EXISTING PARK GATE



**NEW FOOTPATH -
CONSTRUCTION DETAILS
1:20**



500mm ADJACENT TO LEVEL. PATH TO BE MADE LEVEL AND GRADED TO A 1:50 FALL AWAY FROM PATH WHERE NECESSARY BOTH SIDES. GROUND TO BE MADE GOOD AND SEEDED WITH PRO 120.

BODYPAVE 66 PAPER CELLS (or similar approved) FILLED TO WITHIN 5mm OF THE SURFACE WITH 60x40 ROOTZONE THEN SEEDED 60mm CONSOLIDATED 60x40 ROOTZONE MATERIAL TENSAR TRAXX TX160 GEOGRID 150mm THK - TYPE 3 TERRAM 700g.

17. ANY PROTECTION FENCING MUST BE SECURELY FIXED AND FORMED IN SUCH A WAY TO FORM A BARRIER IN PARTICULAR TO YOUNG CHILDREN. CARE SHALL BE TAKEN AT ALL JUNCTIONS WITH THE HIGHWAY. THE CONTRACTOR WILL BE EXPECTED TO PROPERLY MAINTAIN THE INTEGRITY OF HIS FENCING DURING THE PERIOD OF THE CONTRACT.

18. ALL DAMAGE CAUSED TO THE PUBLIC FOOTPATH OR ROAD SHALL BE MADE GOOD TO THE SATISFACTION OF THE COUNCIL'S HIGHWAYS DEPT.

19. THE PUBLIC FOOTPATH AND/OR ROAD SHALL BE KEPT CLEAR, AND MAINTAINED CLEAR OF SITE DEBRIS AND MUD ETC. FOR THE DURATION OF THE CONTRACT.

20. THE STEELWORK FABRICATOR MUST VISIT THE SITE TO VERIFY ALL DIMENSIONS & DETAILS.

21. THE CONTRACTOR SHALL SUBMIT FABRICATION DRAWINGS FOR APPROVAL PRIOR TO ANY FABRICATION.

22. SITE WORKING HOURS SHALL BE IN 8:00-16:00 MON-FRI