

# Streets and Walkways Sub (Planning and Transportation) Committee

Date: TUESDAY, 21 JUNE 2016

Time: 11.30 am

Venue: COMMITTEE ROOMS, 2ND FLOOR, WEST WING, GUILDHALL

**Members:** Christopher Hayward (Chairman)

Graham Packham (Deputy

Chairman)

Deputy John Barker (Ex-Officio

Member)

Randall Anderson Emma Edhem Marianne Fredericks Alderman Alison Gowman (Ex-Officio

Member)

Deputy Brian Harris Deputy Alastair Moss

Jeremy Simons (Ex-Officio Member)

Gregory Jones QC

Tom Sleigh

**Enquiries:** Amanda Thompson

tel. no.: 020 7332 3414

amanda.thompson@cityoflondon.gov.uk

Lunch will be served in Guildhall Club at 12.30PM NB: Part of this meeting could be the subject of audio or video recording

John Barradell
Town Clerk and Chief Executive

#### **AGENDA**

#### Part 1 - Public Agenda

- 1. APOLOGIES FOR ABSENCE
- 2. MEMBERS' DECLARATIONS UNDER THE CODE OF CONDUCT IN RESPECT OF ITEMS ON THE AGENDA
- 3. MINUTES

To agree the public minutes and summary of the meeting held on 9 May 2016.

For Decision (Pages 1 - 4)

4. OUTSTANDING REFERENCES

To receive the list of outstanding references.

For Decision (Pages 5 - 6)

- 5. REPORTS OF THE DIRECTOR OF THE BUILT ENVIRONMENT:
  - a) Mayor's Vision for Cycling Quietways (Pages 7 34)

**For Decision** 

b) Bloomberg Development - Issues Report (Pages 35 - 36)

For Decision

- 6. QUESTIONS ON MATTERS RELATING TO THE WORK OF THE SUB COMMITTEE
- 7. ANY OTHER BUSINESS THAT THE CHAIRMAN CONSIDERS URGENT
- 8. **EXCLUSION OF THE PUBLIC**

MOTION – That under Section 100A(4) of the Local Government Act 1972, the public be excluded from the meeting for the following items of business on the grounds that they involve the likely disclosure of exempt information as defined in Part I of Schedule 12A of the Local Government Act as follows:-

For Decision

#### Part 2 - Non-public Agenda

- 9. NON-PUBLIC QUESTIONS ON MATTERS RELATING TO THE WORK OF THE SUB COMMITTEE
- 10. ANY OTHER BUSINESS THAT THE CHAIRMAN CONSIDERS URGENT AND WHICH THE SUB COMMITTEE AGREES SHOULD BE CONSIDERED WHILST THE PUBLIC ARE EXCLUDED

### STREETS AND WALKWAYS SUB (PLANNING AND TRANSPORTATION) COMMITTEE

#### **Monday, 9 May 2016**

Minutes of the meeting of the Streets and Walkways Sub (Planning and Transportation) Committee held at Committee Rooms, 2nd Floor, West Wing, Guildhall on Monday, 9 May 2016 at 1.45 pm

#### Present

#### Members:

Randall Anderson
Emma Edhem
Marianne Fredericks
Deputy Brian Harris
Christopher Hayward (Chairman)
Gregory Jones QC
Graham Packham (Deputy Chairman)
Tom Sleigh

#### Officers:

Simon Glynn
Sam Lee
Simon Owen
Rob Oakley
Darshika Patel
Alan Rickwood

- Department of the Built Environment
- Department of the Built Environment
- Chamberlain's Department
- Department of the Built Environment
- Chamberlains
- City of London Police

#### 1. APOLOGIES FOR ABSENCE

Apologies for absence were received from Deputy Alastair Moss.

### 2. MEMBERS' DECLARATIONS UNDER THE CODE OF CONDUCT IN RESPECT OF ITEMS ON THE AGENDA

There were no declarations of interest.

(At the conclusion of this item, Deputy Brian Harris, in the Chair, proposed a short adjournment to enable those Members voting in both the elections of Chairman and Vice-Chairman of the Streets and Walkways Sub-Committee and the Guildhall School Board (which was meeting at the same time) time to join the meeting.

The meeting adjourned at 1.50pm and resumed at 1.55pm.

#### 3. ELECTION OF CHAIRMAN

RESOLVED – That Christopher Hayward be elected Chairman in accordance with Standing Order 29 for the ensuing year.

On being elected, the Chairman expressed thanks to the Committee for its support.

The Chairman thanked the immediate past Chairman for her contribution to the work of the Committee.

#### 4. ELECTION OF DEPUTY CHAIRMAN

RESOLVED – That Graham Packham be elected Deputy Chairman in accordance with Standing Order 30 for the ensuing year.

On being elected the Deputy Chairman expressed thanks to the Committee for its support.

The Chairman thanked the immediate past Deputy Chairman for his contribution to the work of the Committee.

#### 5. TERMS OF REFERENCE

RESOLVED – That the Sub-Committee terms of reference be noted.

#### 6. MINUTES

The minutes of the meeting held on 4 April were agreed as a correct record.

#### 7. OUTSTANDING REFERENCES

RESOLVED – That the list of outstanding references be noted.

#### Parking for Motorcycles

The Sub-Committee noted that this had moved into the 2016/17 work programme and included in the restructured City Transportation teams work plan and asked that this not be allowed to slip.

#### Collisions and Casualties

The CoLP reported that the provisional data for all casualties in the 2015 Calendar year was very similar to the overall figure for 2014 (387 casualties compared to 394 in 2014).

There was however a significant reduction in the number of people reported as being killed or seriously injured (1 Fatal and 42 Serious in 2015 compared to 4 Fatal and 51 Seriously injured in 2014).

Within that KSI figure was a 52% reduction in Cyclist KSI casualties (1 Fatal and 10 Serious compared to 3 Fatal and 20 Serious in 2014), and a reduction in Motorcyclist KSI casualties of 33% (6 to 9 in 2014).

Overall Pedestrian casualties at 116 remained similar to 117 in 2014.

Overall Cyclist casualties remained similar at 138 compared to 140 in 2014.

Overall Motorcyclist casualties at 53 were significantly down compared to 80 in 2014.

Provisional figures for January and February 2016 suggested the above trends were continuing.

The Committee asked if this information could be circulated as a written document in future.

#### Swan Pier

A member of the Committee expressed concern at the length of time being taken to make the structure safe and was advised that a report would be coming to the next meeting.

#### 8. REPORTS OF THE DIRECTOR OF THE BUILT ENVIRONMENT:-

### 8.1 Gateway 4 - Middlesex Street Area - Redesign of new public space in Artizan Street post ramp demolition (phase B)

The Sub-Committee considered a Gateway 4 report of the Director of Built Environment in relation to the redesign of new public space in Artizan Street.

The Sub-Committee was advised that the removal of the ramps had left the site area in a temporary state (temporary surfacing, drainage, unsightly concrete finishes) with ponding issues, illegal parking and risks of traffic over-runs (concrete blocks had been installed on a temporary basis to control vehicle access and ensure safety) and local residents, occupiers and Ward Members were keen to see the transformation of the space completed.

Members raised a number of questions in relation to the positioning of the green walls, whether or not seating had been requested, the scheduling of the works and the reasons for the increase in the project cost.

#### **RESOLVED –** That approval be granted for:

- 1) The enhancement proposals to be taken forward to Gateway 5;
- 2) The statutory consultation process to be undertaken on the proposed traffic management change of the redundant section of carriageway;
- £43,000 of staff costs and fees to take the scheme to Gateway 5, funded from the Section 106 contribution from the 100 Bishopsgate Development; and
- 4) The inclusion of a new canopy to the Petticoat Tower entrance as well as a health and leisure outdoor equipment in the project scope identified through consultation

### 9. QUESTIONS ON MATTERS RELATING TO THE WORK OF THE SUB COMMITTEE

Cycle Super Highway – Tudor Street

In response to a question concerning the action taken by TfL to open the Cycle Super Highway despite the Court of Common Council rescinding the previous decision of the Streets and Walkways Sub-Committee, the Chairman reported that the City had been asked by the Inns to convene an urgent meeting with TfL and all interested parties to try and find a solution.

Members expressed a number of concerns about TfL's actions, the safety of the area and the City's liability should there be an accident and asked for officers' views of TfL's Road Safety Assessment of what they had built.

Members reported that several collisions and near misses had been seen between vehicles leaving Tudor St crossing the cycle super highway, and several vehicles leaving Tudor St had been seen to turn left and drive up the cycle lane, rather than turning into the northbound vehicle lane.

Members considered the fact the mitigation measures had not been implemented was contributory factor to problems in the area and questioned the City's liability if there was an accident. A further question was also raised concerning what consent TfL had to undertake their works in Bridewell Place.

It was agreed that the responses to the questions raised should be circulated to Members after the meeting to enable officers to fully investigate the issues.

10. **ANY OTHER BUSINESS THAT THE CHAIRMAN CONSIDERS URGENT** There were no items of urgent business.

The meeting ended at 3.00 pm

Contact Officer: AmandaThompson tel. no.: 020 7332 3414

amanda.thompson@cityoflondon.gov.uk

Outstanding References - Streets and Walkways Sub Committee

Date	Action	Officer responsible	To be completed/ progressed to next stage	Notes/Progress to date
9 May 2016	Parking for Motorcyclists  As part of the review of fees and charges for car parks, consideration be given to the implications on motorcycle parking.  A further report to be submitted to the Sub Committee regarding the framework for charging, provision of more parking bays and theft of motorcycles	Director of the Built Environment  Director of the Built Environment	Ongoing	March 2016 Update The parking policy for motor cyclists has been held up pending the outcome of the review of car parking availability. It is proposed this matter now be moved to the 2016/17 work programme and included within the restructured City Transportation teams work plan.
Ongoing action	20mph speed limit	COLP	Ongoing	To receive regular updates.
22 February 2016 9 May 2016	Swan Pier  Swan Pier area is to be tidied up in conjunction with the delivery of the Fishmongers Ramp project which is due for completion Summer 2016	Director of the Built Environment	Summer 2016	To receive any update
22 February 2016 9 May 2016	Cloth Fair Noise Disturbance  This item was withdrawn from the meeting but officers undertook to treat the matter as urgent.	Director of the Built Environment	Ongoing	The street has been monitored for a week over the Easter period and discussions taking place with Environmental Health following which a further report will be presented to Committee in Summer 2016.
4 April 2016 9 May 2016	1 Angel Court Improvements GW4-5 V9  Members asked if the height of the benches could be raised,	Director of the Built Environment		To receive any update.

Page 5

Outstanding References - Streets and Walkways Sub Committee

	both to improve the comfort for less mobile users and to further deter skateboarding. Officers undertook to investigate the proposal.		
4 April 2016 9 May 2016	Street Lighting Review  Members asked that details of the IT project and the work that	Director of the Built Environment	To receive any update
	would be required to fit the hubs be circulated to members of the Committee as well as included in the report for its consideration at Projects sub-committee.		

Committees:	Dates:	Item no.
Streets and Walkways Sub-	21/06/2016	
Committee		
Projects Sub-Committee	29/06/2016	
Health and Wellbeing Board (for info)	16/09/2016	
Subject:	Gateway 5	Public
Mayor's Vision for Cycling - Quietways	Authority to Start Work	Public
Report of:	•	For Decision
Director of the Built Environment		FOI DECISION

#### **Summary**

#### **Dashboard**

Project status: Green

Timeline: Construction to commence in July 2016 for six months

Current approved budget: £146,654\*

Spend to date: £152,000\*

Total estimated cost: £1.21M, which includes an increase of nearly £260k (fully

funded from TfL)

Overall project risk: Medium

In July 2015, a Gateway 3/4 Report was considered by the Streets & Walkways and Project Sub-Committees. At the meeting Members approved the following:

- 1. Changes to the alignment and the extent of the Quietways network. They agreed to postpone parts of the network (in the east of the City) to possibly beyond 2016. See Appendix 5.
- 2. Progress with the recommended measures and the undertaking of wider public consultation and detailed design. See Appendix 6A and 6B.
- 3. Proceed with the implementation of an experimental closure of the northern end of Moor Lane. See Appendix 6B.

#### **Progress to date**

Public consultation was carried out in November and December 2015. The responses have now been analysed and a summary can be found in Appendix 1. Detailed design, taking into account these responses has been completed and as a result, amendments have been made. Appendices 2A and 2B illustrate the overall proposals and two copies of the detailed plans are available in the Members Reading Room for further review.

The experimental closure of the northern end of Moor Lane has not been implemented because Islington is not supporting this proposal. It has therefore been necessary to amend the design and retain Moor Lane open.

Officers have continued to engage with TfL and the Mayor's Cycling Commissioner (at the time) to review further Quietways routes in the City and the reconsideration of the routes previously deferred by Members. From this engagement, it is now proposed to

<sup>\*</sup> excludes the revenue costs associated with the deferred routes

proceed with a section of the previously postponed route (from Wilson Street to Bishopsgate) and Gateway 5 approval is sought as part of this report. The revised route alignment can be seen in Appendix 3.

It is proposed that the City's term contractor, JB Riney, and where relevant, the utility and equipment owners are used to implement the proposals.

#### Recommendations

It is recommended that:

- 1. Authority to start the work is approved, at a total estimated cost of £1.21M, funded from TfL's Grid programme.
- 2. The budget adjustment as detailed in Appendix 4 is approved.
- 3. The Quietways route from Wilson Street to Bishopsgate and the related measures be approved at a total estimated cost of £22,000 (which is included in the above £1.21M), funded from TfL's Grid Programme.
- 4. The Director of the Built Environment be authorised to accept and use any further funding towards this project that may be made available by TfL.

#### **Main Report**

## 1. Design summary

- 1. The majority of the proposed measures are minor in nature such as new traffic islands, road markings, signage, street lighting, carriageway resurfacing and wayfinding. There are, however, also some significant measures such as small sections of segregated cycle lanes and raised carriageways. They have been designed and amended to take into account the responses from the public consultation and the further engagements with a number of key stakeholders such as TfL, the Barbican Association and the Smithfield Market Traders Association.
- A summary of the measures on the approved Quietways network are detailed below and are illustrated in Appendices 2A and 2B. Details plans will be provided in the Members' Reading Room for review.
  - i. Alterations to kerb lines to widen the footway/narrow the carriageway, and to reduce junction sizes. This would reduce traffic speeds, improve pedestrian crossing convenience and provide opportunities for on-street bicycle parking and tree planting.
  - ii. Alterations to road markings and traffic signs, including new Quietways wayfinding signs and road marking.
  - iii. Street lighting improvements to create a safer and a more inviting environment for cyclists and the general public. These will be implemented in Hosier Lane, Middle Street, Long Lane, Moor Lane, Wood Street, and Gresham Street. A better and smoother road surface. This will be carried out in Smithfield Street, Hosier Lane, Cloth Fair, Middle Street, Wood Street, Gresham Street and King Street. Resurfacing works have already been carried out in Queen Street and a small section of Beech Street as part of a general maintenance programme.
- iv. Increasing the cycle only waiting areas (advance stop lines) at signalised

- junctions from 5m to 7.5m. This will provide more space and cleaner air ahead of motor vehicles for the increased numbers of cyclists that are expected.
- v. Permitting contra-flow cycling on West Smithfield and Smithfield Street. The design includes a combination of road markings and kerbs to segregate cyclists from motor vehicles. This would ensure the facilities provided are as safe as possible, in a location with a high proportion of goods vehicles.
- vi. The existing traffic island in West Smithfield at the junction with Smithfield Street wil be removed to improve the layout and the kerbs will be extended to provide space for the relocation of a loading bay.
- vii. Raised carriageway at Smithfield Street and Milton Street to reduce speeds and to improve road safety. Appropriate double yellow lines where necessary will be included.
- viii. All existing loading and parking provisions have been retained or relocated.
- 3. Officers have been liaising with officers in Islington Council since March 2015 on the experimental closure of Moor Lane, but have so far been unsuccessful in obtaining their agreement. Their agreement is required because Moor Lane is a boundary Street with dual highway and traffic responsibilities. It has therefore been necessary to amend the design and retain Moor Lane open.
- 4. The measures will be implemented using the City's approved material palette for carriageways, footways, traffic signs and road markings as well as the Quietways wayfinding signage (as approved at Committee in July 2015).

#### Extension of the network

- 5. At the Gateway 3/4 stage, Members approved the deferral of the cycle network to the east of the City. The two main reasons for this were a). It was not possible to continue the route through private land or on TfL's Bishopsgate and b). Concern with the ability for some of the narrow streets to be used as a strategic cycle link between two cycle superhighways.
- 6. Since then, officers have continued to engage with TfL and the Mayor's Cycling Commissioner (at the time). As a result, City officers have been made aware of TfL's proposals to improve the Bishopsgate/Primrose Street junction to provide better cycling provisions by December 2016. There is also the potential to connect to a future cycle network to the east of the junction, a network that officers had not been made aware of previously.
- 7. The proposal for this section of the network was evaluated prior to the Gateway 3/4 approval but discounted because the information above was not known. The measures now proposed includes: improving the street lighting, road markings and other minor works. The proposals are very minor and therefore no material impacts are envisaged. The total estimated cost to deliver this is £22,000 (£20,000 works & £2,000 staff costs).
- 8. In view of this new information, it is now recommended that this section of the route is reinstated and that, given, the very minor nature of the proposals,

		these be approved t	for implement	ation.		
2.	Dolivory					
۷.	Delivery team	Function Organisation		Organisation	n	
		Project Management DBE City T			ansportation team	
		Road Network Performance			•	
		Management & Safety  DBE City T			ransportation team	
					olic Realm team	
		Design & Build Supervision DBE Highways team				
		Construction			ty's term contractor)	
		Planting & Greenery	arommo	Open Space	s Department	
		Project Sponsor & Promanagement	gramme	TfL		
3.	Programme and key	Stage			Target date	
	dates	_			Target date	
	aatoo	Gateway 5 authorisati			June 2016	
		Complete Pre-Constru			June 2016	
		Statutory consultation TMO's  Mobilisation of contractor			July 2016 July 2016	
		Distribution of information letters			July 2016	
		Construction			July - Dec 2016	
4.	Outstanding	D: 1			The state of the s	
4.	Outstanding risks	Risk	Impact	Likelihood	Mitigation	
4.	_	Risk  Delivery of signal changes due to programming issues with the TfL signal team and London Wall Place development	Impact Medium	Likelihood	Stay on top of progress with the development tear and TfL signal team.	
4.	_	Delivery of signal changes due to programming issues with the TfL signal team and London Wall Place			Stay on top of progress with the development tear	

Objections to statutory consultation on the proposed traffic management orders	High	Medium	Informal consultation has already taken place with frontages and key stakeholders. A summary of the outcome is detailed in Appendix 1.
Works extend beyond GLA target delivery date of 31 December 2016	Medium	Medium	Engage contractor as early as possible.
Deferral of decision may jeopardise funding/spend by 31 March 2017	High	Medium	Member briefings.

#### 5. Budget

- 9. The Quietways project within the City was initially estimated at £2.3 million and TfL have confirmed their commitment to meeting these costs in principle. However TfL will be updating the costs to deliver the wider Quietways programme. It is therefore anticipated that this committed funding will be reduced to the amount now needed by the City.
- 10. At the Gateway 3/4, Members approved the deferral of a section of the Quietways network (which comprises two schemes) for the reasons as detailed in para 5. It should be noted that officers had already spent a total of £45,514 of revenue on these two schemes, which has been funded from TfL's Grid programme.
- 11. Detailed financial implications for this project, including the re-instatement of a section of the previously deferred route (Wilson Street to Bishopsgate) are shown in Appendix 4 and are summarised in the table below.

Description	Total Estimated Cost (£)
Spend to date - Evaluation	152,000
Implementation (estimated)	
Current approved routes	1,036,000
Wilson Street to Bishopsgate route	22,000
Total implementation costs	1,058,000
Total estimated Project Cost	1,210,000
Total TfL Grid funding requirement	1,210,000

12. It should be further noted that since the Gateway 3/4 report was approved, the total estimated cost has increased from £950,025\* to £1.21M (an increase of nearly £260k). The reason for this increase relates to additional or modified measures added in as a result of the public consultation and engagement as well as further detailed design information since the Gateway

		3/4. Further details of the cost changes are detailed in table 5 of Appendix 4.  * excludes the revenue costs associated with the deferred routes		
6.	Success criteria	<ul> <li>i. The type and level of interventions respond to stakeholder needs.</li> <li>ii. The measures implemented are compliant with the agreed levels of service for Quietways.</li> <li>iii. The works are completed by December 2016.</li> <li>iv. The costs are within agreed budgets.</li> <li>v. Increased number of cyclists using the Quietways network.</li> </ul>		
7.	Progress reporting	Monthly updates to be provided via Project Vision and any project changes will be sought by exception via Issue Report to Spending and Projects Sub Committees		

### **Appendices**

Appendix 1	Consultation outcome and response breakdown
Appendix 2 A/B	Overview of proposals on approved Quietways network
Appendix 3	Overview of the proposed Quietways network in the City
Appendix 4	Financial implications
Appendix 5	Quietways network as approved at Gateway 3/4
Appendix 6 A/B	Quietways measures as approved at Gateway 3/4

### **Contact**

Report Author	Mark Kelder
<b>Email Address</b>	Mark.kelder@cityoflondon.gov.uk
Telephone Number	0207 332 3970

#### **APPENDIX 1: Consultation outcome and response breakdown**

#### A. Consultation details

Stakeholders and occupiers along the routes were given an opportunity to express their views on the proposals between Thursday 12 November and Sunday 6 December 2015. A total of 2482 people and organisations were contacted:

- 957 letters were hand delivered to frontagers and City occupiers
- 1405 letters were emailed to the residents of the Barbican Estate
- 44 letters were emailed to key and local stakeholders including TfL, Cycling and pedestrian groups, Access Group, Smithfield Market Superintendent, SMTA, Barbican Association, the emergency services, and many others.
- 69 letters were posted to City of London Members who are Ward Member of the affected wards or sit on the Barbican Residential Committee or the Streets and Walkways Sub (Planning and Transportation) Committee
- 6 letters were emailed to London Borough of Islington Councillors who are Ward Councillor of the affected wards
- 1 letter was sent to the Service Director for Planning & Development, London Borough of Islington (LBI).

The letter included a link to a 2-page section on the City of London website with the details of the proposals. This website was also promoted on the homepage of the City of London website, the intranet, on social media platforms, and featured in the weekly DBE Streetworks newsletter which is sent to over 1,100 recipients. In addition, consultation posters were sited at 7 locations along the routes to further engage with the wider public.

Following this, further discussions continued with a number of stakeholders, including the Barbican Association, the SMTA and the Smithfield Market Superintendent. This included a further meeting with the SMTA and the Superintendent in May 2016 and officers consider that all the issues and concerns raised have now been addressed. A further meeting also took place with Ward Members of Cripplegate and Aldersgate and, the Barbican Residents Association in May 2016. As a result of this, further minor additional comments have been raised which officers believe have now been addressed or will be separately considered as part of other projects and activities.

#### B. Consultation outcome

A total of 65 responses were received. 24 (37%) responses came from residents, 7 (11%) from key stakeholders, 3 (5%) from businesses and 3 (5%) from Members. The remainder did not state their relation to the City or the consultation.

9 (14%) of respondents stated that they are cyclists.

The key stakeholders who responded include the Barbican Estate Office (BEO), the Smithfield Market Tenants' Association (SMTA), the London Taxi Drivers Association (LTDA), the Barbican Association, CrossRail, London Cycling Campaign (LCC) and TfL (London Taxi and Private Hire).

Support for the project in principle?				
Response	Number	Percentage		
Yes	29	45%		
Neutral/ specific	14	22%		
No	13	20%		
Not specified	9	14%		
total	65	100%		

From the above table, it can be seen that there is a least twice the level of support for the overall cycle Quietways proposals compared to those who are against.

A further 8 (12%) of respondents stated that the proposals do not go far enough and that more is required to be undertaken to provide safer conditions for new and beginner cyclists. 11 (17%) respondents stated that they are not in favour of the alignment of the routes, whilst 6 (9%) expressed concerns about the air quality and 9 (14%) about cyclists' behaviour including cycling on pavements, not providing right of way, and ignoring red lights etc.

#### C. Responses to specific proposals and design considerations/alterations

Many comments received were aimed at specific proposals, including at the three locations where significant measures are proposed as described in the gateway 3/4 report. It should be noted that the number of responses on these specific proposals are very low and therefore the percentages can be significantly influenced by just a few responses. It should also be noted that alterations have now been incorporated into the design which has mitigated the majority of the concerns raised.

A summary of the main concerns across the 6 different locations are detailed as follows:

1. Proposed contraflow cycle lanes in West Smithfield and associated measures required at the junction with Farringdon Street

Response to proposals	Number	Percentage
in favour	4	31
not in favour	9	69
total	13	100
Specific comments	Number	
concerns with visibility	5	
concerns with reduced capacity	4	
concerns with safety on TLRN	4	
concerns with removing loading bays	3	

- The SMTA and CrossRail objected to the removal of the loading bays, which
  are also being utilised as holding areas for construction traffic for the
  CrossRail sites during the day. These have now either been retained or
  repositioned with no overall loss.
- 5 respondents are concerned about the visibility at the junction of Snow Hill and West Smithfield, where right turning vehicular traffic may not expect or see contra-flow cyclists (from the right). Minor alterations to the alignment are now proposed to improve sightlines.
- The SMTA and the LTDA objected to the removal of the second westbound lane at the junction of Snow Hill and Farringdon Street. The revised design now retains the two lanes at the junction. It has also been acknowledge that this junction may change as a result of TfL's extension to the North-South Cycle Superhighway.
- 2. Proposals at the junction of Smithfield Street and Hosier Lane

Response to proposals	Number	Percentage
in favour	2	22
not in favour	7	78
total	9	100
Specific comments	Number	
concerns with visibility	1	
concerns with presence of HGV's	2	
concerns with traffic speed	2	
concerns with manoeuvrability	1	

 The SMTA and the LCC both expressed concerns with cyclists in both directions having to cross Smithfield Street which is often subject to fastmoving traffic including a high number of HGV's, and suggested to maintain the existing one-way flow for all traffic in this area. The design has been amended to include a raised carriageway and changes to kerblines to reduce traffic speed and improve sightlines. 3. Proposals at the junction of Long Lane and Aldersgate Street

Response to proposals	Number	Percentage
in favour	0	0
not in favour	5	100
total	5	100
Specific comments	Number	
concerns that not enough is done	3	
concerns with cyclists' behaviour	1	
junction Cloth Street /Long Lane	3	

- There were a number of suggestions for further improvements that include low level cycle signals and segregation at this junction. Unfortunately, due to the timescales involved to deliver these measures, it is not possible to include these as part of the Quietways project without impacting on the programme as set out by the GLA for completion by 31 December 2016. However, these will be considered separately, when opportunities arise.
- There were requests to discourage vehicles from entering the advisory cycle lane. The design has been amended to include a mandatory cycle lane.
- 4. The proposed closure to motor vehicles on Moor Lane at the junction with Chiswell Street

Response to proposals	Number	Percentage
in favour	4	31
not in favour	9	69
total	13	100

- The experimental closure would have tested the effectiveness of the proposals but this is no longer being taken forward as it has not been possible to obtain Islington's agreement so far. The design has therefore been amended.
- 5. At the proposals for the junction of Moor Lane and Fore Street

Response to proposals	Number	Percentage
in favour	1	17
not in favour	5	83
total	6	100

 Concerns from the Barbican residents about conflicts between cycles and pedestrians. As a result of further engagement with the Barbican Association, some amendments to reduce this conflict are now proposed. This comprises of footway widening on the corner with Fore Street, providing route guidance paving and markings to guide cyclists and repositioning of drop kerbs to discourage cyclists/encourage them to re-join the carriageway at more appropriate locations. Consideration of a short cycle lane on the approach to Moor Lane is still being investigated but if suitable, this will be included.

6. The proposed cycle lane removal in King Street and Queen Street


Response to proposals	Number	Percentage
in favour	0	0
not in favour	5	100
total	5	100
Specific comments	Number	
concerns with cycle lane removal	4	
safety concerns at junction with Queen		
Victoria Street	3	
concerns with the shared spaces	3	


- The removal of the existing cycle lanes on King Street and Queen Street was not supported. However, the London Cycle Design Guidance recommends that cycle lanes should be no narrower than 1.5m and for ASL lead-in lanes, a minimum of 1.2m. The existing cycle lanes on King Street are 1.1m and there are no opportunities to widen this due to limited road width. Narrow cycle lanes represent a low level of service for cyclists and cannot cope with the growth in cycle numbers. They provide limited lateral clearance from vehicles and encourage cyclists to cycle close to the kerb. The removal of the cycle lanes encourages cyclists to take a better road positioning and with the quieter nature of King Street, the removal is considered appropriate. The ASL area will however be retained.
- The existing cycle lanes in Queen Street have recently been widened in line with the guidance and therefore these will remain.
- Other measures requested to mitigate the safety concerns raised at the junction with Queen Victoria Street and the shared spaces on either side of Cannon Street will not be included as part of this project because of the current building activity taking place. However, if opportunities allow, these will be considered separately.


# D. <u>Comments and suggestions received that are not taken forward under the Quietways programme but can be considered when opportunities arise</u>

Location	Suggestion for further improvement	Number
East of proposals	Link CSEW with Aldgate	1
West of proposals	Request for a separate phase for cycles at Holborn Circus	1
Signalised junctions	Use of early-start low level cycle traffic signal	1
	Move the route of the Quietway to cover all of Wood Street,	
Alignment	then Bread Street, Watling Street and into the no-vehicle	
Aligninent	section of Queen Street if the City wants to remove the	
	advisory cycle lanes on King Street and Queen Street	1
	Include the prohibition of cycling on any pavement. The	
General	creeping inclusion of signage which signifies the permitted	
General	joint use of pavements by cyclists and pedestrians is a lazy	
	and dangerous solution to providing facilities for cyclists.	1
General	Use sufficient signage along the route and to provide clarity at	
General	shared surfaces in the City	2
General	Enforcement of ASL's	1
	All proposed road changes are affecting taxi drivers and the	
	taxi trade, incl the Bank Junction scheme. Their livelihoods	
General	are being destroyed in front of their eyes because no	
	consideration seems to be given to people who rely on the	
	roads for a living and drivers who have no alternative.	1
West Smithfield	Make right turn into West Smithfield safer by introducing a	
(market)	traffic island in Farringdon Rd	1
West Smithfield	Create permeability in West Poultry in both directions / drop	
(market)	kerb on the cycle side of segregating islands	1
West Smithfield	Remove metal barrier near the gate to St Bart's (that forms	
(Ambulance station)	part of the Ring of Steel)	2
,	Allow cycling through Smithfield Market to improve cycle	
Smithfield Market	access to Cowcross St and St. John St where there are many	
	employers	1
	Increased numbers of cyclists will cause conflict with	
llesier Lene	pedestrians walking in the carriageway due to narrow	
Hosier Lane	footways in Hosier Lane, as well as with vehicles accessing	
	property.	1
Clath Fair	Cloth Fair is too narrow to accommodate motor traffic and	
Cloth Fair	should be made access only (model filter)	2
	Ensure coordination with the proposals in the Area	
Cloth Foir	Enhancement Scheme, announced a few years ago, and the	
Cloth Fair	Cloth Fair Noise Disturbance Proposals, currently being	
	consulted on.	1
	As many pedestrians are walking or standing in the road,	
Cloth Fair / promotion	notices should be put up to ask cyclists to use their bell more	
·	often	1
Long Lane /	Introduce double yellow line waiting restrictions and peak	
Aldersgate	hour loading restrictions on north side of Long Lane	1
Aldersgate /Beech	Some "semi segregation" using cats eyes or slightly	
Street	raised/bumpy road surface few metres into Beech Street	1

	immediately after the pedestrian crossing area	
Aldersgate /Beech	Introduce low level cycle signals for an early start / elephants	
Street	footprints across junction	1
Beech Street	Introduce segregation	1
Decel Office	Requested traffic calming measures to reduce speed and	
Beech Street	encourage better behaviour especially towards pedestrians	
(cinemas)	using the crossing	1
Decah Ctuant	Right turn into Silk Street is difficult, and it was suggested to	
Beech Street	relocate the zebra crossing in Silk Street by a few yards	
(cinemas)	further south	1
Moor Lane	No right into and out of Moor Lane as an alternative	1
	Suggested to change the one-way operation in Finsbury St	
Moor Lane	and Moor Lane in order to keep the taxi ranks in Ropemaker	
	Street operating efficiently	1
Moor Lane/Fore Street	Provide segregated cycle tracks on southern Moor Lane	1
Moor Lane /Fore	,	I
Street	Change priority and install the give way marking on the eastern arm / raise the junction	1
Wood Street, Fore	Request for more street furniture and trees in the footway to	I
Street and Moor Lane	deter footway cycling	1
Street and Woor Lane	The markings encouraging cyclists to cross the lane	<u> </u>
London Wall /Wood	diagonally from the left should be removed and the radius on	
St	the bend tightened to ensure there is no space for a vehicle to	
Ot .	get on the outside of a cyclist.	1
	Introduce new ped crossing on east arm, new ASLs on	<u>'</u>
London Wall /Wood	London Wall, remove stagger crossing, introduce no loading	
St	restrictions /armadillos south of junction	1
London Wall /Wood	Introduce elephants footprints across junction also in n/b	•
St	direction / introduce lead-in cycle lanes to ASLs	1
	Make Wood Street north of Gresham Street one-way, and	
Gresham St /Wood St	provide segregated cycle facility in Wood Street and Gresham	
	Street	1
One als are Ot M/a a d Ot	Change priority and install the give way marking on the	
Gresham St /Wood St	western arm / raise the junction	1
Queen Street	Introduce area wide model filtering: between Trump Street	
(Cheapside /Queen	and Cheapside, and between Pancras Lane and Queen	
Victoria St)	Victoria Street.	2
	There should be segregated cycle lanes with differential kerbs	
Queen Street	in the shared surface areas in Queen Street and over Cannon	
	Street	1
	Please remove the last parking space at the southern end of	
	Queen Street. It makes it hard for cyclists to see what	
Queen Street	pedestrians are doing on the kerb where the cyclist will	
	shortly turn left into College Street to access the calm safe	
	bike stand area near Whittington Gardens.	1
Queen and King Street	Stepped cycle track	1
	Publish maps of recommended cycle routes (with the Boris	ı
Promotion	bike stations marked) and update them as you make progress	1
		-







#### **APPENDIX 4 FINANCIAL IMPLICATIONS**

Table 1 shows the total spend-to-date. As officers spent more on some tasks than originally budgeted for it is necessary to seek a Budget Adjustment as shown in table 2, as part of this report. Table 3 and table 4 show the total estimated costs for the implementation of the Quietways measures after Gateway 5 by December 2016. The total costs of £1.21M will pay for the construction works, the maintenance of the tree near the ambulance station for 5 years by Open Spaces Department, the fees and staff costs, and will be fully funded by the TfL's Grid programme. Table 5provides details of the cost increase since Gateway 3/4.

Table 1: Spend to Date - Evaluation				
Description	Approved Budget (£)	Expenditure (£)	Balance (£)	
P&T Staff Costs	39,682	41,301	(1,618)	
Env Servs Staff Costs	2,000	4,102	(2,102)	
Fees - Route 4	7,624	7,624	-	
Revenue	32,357	32,357	-	
Total Route 4 (Q – from Farringdon St to Silk St)	81,663	85,384	(3,720)	
P&T Staff Costs	26,950	31,512	(4,562)	
Env Servs Staff Costs	3,000	4,582	(1,582)	
Fees - Route 6	16,550	16,031	519	
Works - Route 6 Moor Lane Experiment (not progressed)	4,000	-	4,000	
Revenue	14,491	14,491	-	
Total Route 6 (Q11 – Upper Thames St to Chiswell St)	64,991	66,616	(1,625)	
TOTAL Quietways	146,654	152,000	(5,345)	


Table 2: Budget Adjustment required				
Description	Approved Budget Adjustment (£)		Revised Budget (£)	
P&T Staff Costs	39,682	1,618	41,301	
Env Servs Staff Costs	2,000	2,102	4,102	
Fees - Route 4	7,624	0	7,624	
Revenue	32,357	0	32,357	
Total Route 4 (Q – from Farringdon St to Silk St)	81,663	3,720	85,384	
P&T Staff Costs	26,950	4,562	31,512	
Env Servs Staff Costs	3,000	1,582	4,582	
Fees - Route 6	16,550	(519)	16,031	
Works - Route 6 Moor Lane Experiment (not progressed)	4,000	(4,000)	0	
Revenue	14,491	0	14,491	
Total Route 6 (Q11 – Upper Thames St to Chiswell St)	64,991	1,625	66,616	
TOTAL Quietways	146,654	5,345	152,000	


Table 3: Implementation	
Description	Total Estimated Cost (£)
Works Costs	875,000*
Fees	45,000
Staff Costs	135,000*
Maintenance Costs	3,000
Total	1,058,000


<sup>\*</sup> Includes costs (£20,000 for works and £2,000 of staff costs) associated with the proposed re-instatement of a section of the deferred route.

Table 4: Funding Strategy	
Spend to date – Evaluation	152,000
Implementation	1,058,000
Total TfL funding requirement	1,210,000

Table 5: Items of significant cost increase since Gateway 3/4				
Proposal/location	Estimate at G3/4 (£)	Estimate at G5 (£)	Increase (£)	Reason for increase
Smithfield Street raised carriageway	0	85,000	85,000	Raising and narrowing of carriageway to improve safety to reduce speeds and improving visibility in response to consultation comments
Extension of the West Smithfield footway/relocation of cctv camera	25,000	60,000	35,000	Increased engineering measures required to accommodate Smithfield Market needs/retain overall loading bays
Ambulance station cycle gap	5,000	30,000	25,000	To provide an improved layout
Moor Lane/Fore Street	5,000	15,000	10,000	To accommodate local safety concerns
London Wall/Wood Street	95,000	170,000	75,000	To accommodate engineering difficulties and additional signal costs
Re-instatement of a section of the route	0	22,000	22,000	To provide improved route connectivity
Total	130,000	382,000	252,000	







Committee(s):	Date(s):
Streets & Walkways Sub Committee	21 June 2016
Projects Sub Committee	29 June 2016
Subject: Bloomberg Development (s278 Highway Changes) - Issue Report No.2: Authority to Pre-Order Material and Place Orders for Preparatory Works in Advance of Gateway 5 Approval	Public
Report of: Director of the Built Environment	For Decision

#### Summary

Due to a recent design change at Cannon Street affecting the proposed highway levels, there is now a need to place orders for additional preparatory works (including utility diversions) in advance of the Gateway 5 approval. The design change has been requested by the developer who is funding the highway works as part of their s278 obligations.

#### Recommendations

In order to ensure that construction can commence in a timely fashion to meet the developer's programme, it is recommended that Members:

- Authorise for orders to be placed for any necessary preparatory works (such as utility diversions) in advance of the Gateway 5 approval provided funding is received from the developer; and
- Agree for construction material (such as Yorkstone paving) with critical leadin times to be pre-ordered before Gateway 5 approval subject to funding being received from the developer.

#### **Background**

The original proposal intended to introduce a flush surface over a large section of Cannon Street such that the footway and carriageway would be at a single level whilst realigning the kerb to widen footway areas where possible.

In introducing a flush surface, a series of bollards would need to be introduced on both sides of Cannon Street to manage the risk of vehicles over-running onto footways and/or underground structures (such as basements) which are not designed to withstand vehicle loading.

In order to minimise clutter and remove the need for the proposed bollards, the design has been revised to retain the kerb upstand along a section of Cannon Street (between Queen Street and Walbrook) such that the footway will be (about 125 mm) higher than the carriageway whilst retaining the proposed kerb realignment to widen footways areas where possible.

Consequently, the utilities that straddle the footway and carriageway now need to be diverted where previously there was no need due to the flush surface (which would have merely required the levels of the utility covers to be adjusted appropriately).

#### **Implications**

Any costs implications from this design change will be borne by the developer as part of their s278 obligations. Urgent enquiries are being made with affected utilities to establish relevant costs, but the order of costs is estimated to be below £250,000 based on experience throughout the City. Any costs increase will be detailed at the Gateway 5 report (expected July 2016).

Utility diversions have a significantly longer lead-in time due to its potential complexity, and this may have an impact on the programme if approval is not granted to place orders in advance of the Gateway 5 approval.

#### Conclusion

Due to the longer lead-in times for utility diversions, orders need to be placed in advance of the Gateway 5 approval to ensure construction can progress in a timely fashion to meet the developer's programme.

Authority is therefore also sought for any other preparatory works and the pre-order of material with critical lead-in times in advance of the Gateway 5 approval subject to funding being received from the developer.

#### **Appendices**

Not applicable

#### **Christine Wong**

Project Manager
Department of the Built Environment

T: 020 7332 1511

E: christine.wong@cityoflondon.gov.uk