**IMPORTANT:-** Licensable activities can take place anywhere within the red line. The position of loose furniture and equipment is shown for diagrammatic purposes only. Firefighting equipment is indicated but may be moved subject to the fire risk assessment carried out under the Regulatory Reform (Fire Safety) Order 2005 or by agreement with the fire officer.

Welfare at work (HSE) -
Guidance for employers on
welfare provisions.

## Maximum site occupancy: 31 people


No. of people at work	No. of toilets	No. of washbasins
1-5	1	1
6-25	2	2
26-50	3	3
51-75	4	4
76-100	5	5

Area	m²	ft²
Gross Internal Area (GIA)	507	5457
Product Collection Area	343	3692

Вау Туре	Quantity
CAEM TN9 Racking	98
(1220 x 1330)	(120)
Unizinc Racking - Dispatch &	
Riders & Consumables Storage	5
Chrome Racking (Bike	1
chargers)	
Chiller	15
True GDM-35-HC TSL01	(14)
(1004Wx759Dx1998H)	
Freezer	7
True GDM-43F-HC TSL01	(7)
(1197Wx759Dx1998H)	
Chest Freezer	0
Walk In Chiller	120ft²
(16ft x 8ft)	
Walk In Freezer	120ft²
(16ft x 8ft)	

LEGEND

- S = Smoke Detector
- FA = Fire Alarm
- FB = Fire Blanket
- CO2 = Fire Extinguisher



PROPOSED GROUND FLOOR LAYOUT PLAN 1:75@A1/ 1:150@A3

_				
	Revision	Date	Ву	Chk
-	First Issued	02.03.22	WN	PT
Α	Revised following Gopuff comments	08.03.22	WN	PT
_				

- All travel distances have been calculated and comply with Table 2 on page 34 of the Approved Document B, Vol 2.
- All alterations to the building fire detection system to be designed and installed to BS 5839 pt1.
- All alterations to the buildings emergency lighting system to comply with BS 5266 pt1.
- Walls and ceilings in circulation spaces to have class 0 surface spread of flames, with class 1
- All new ductwork to be installed as part of requirements stated under part F and to have dampers where penetrating fire rated construction
- Once works are complete the owners and users of the building acknowledge their continuing requirement to carry out continual assessment under the RRO.

LOCATION	HAZARD	LIKLIHOOD	COMMENTS / ACTION	FOLLO ACT
	Live Services	HIGH	Contractor isolate all services prior to commencement and ensure adequate support of existing services during the works	LC
1/2	Working at height	HIGH	Correct selection of MEWP to be utilised at all times including weekly inspections	LO
1 3	Means of Escape	HIGH	Area in front of means of escape to be kept clear for constant access incase of emergency.	LO
4	Slips trips and falls	HIGH	New viryl floors and concrete sealants to be slip resistant. Existing flooring being retained, slip resistance to be reviewed.	LO
1 5	Risk associated with electricution	HIGH	Contractor isolate all services prior to commencement and ensure adequate support of existing services during the works	LO

APPROVED DATE: 0/0/0

**SCOPING** 





171-176 ALDERSGATE STREET LONDON EC1A 4HU

PROPOSED GROUND FLOOR LAYOUT PLAN

Project Number		Drawing Number			Revision	
A00257-SC		110			Α	
Drawn WN	Checked PT		Scale AS SHOWN@A3	Date 08.03.22		
			perty of RPM Consu without formal cons		d may not be	